

## **Pedestrian Ramp Construction Triggers**

The intention of this document is to provide guidance regarding the requirements for pedestrian (curb) ramp\* work to any entity (private or public) performing construction activities (including alterations) within the New York City's right-of-way. Construction of pedestrian ramps, including upgrades and installations, must adhere to the latest version of the NYCDOT highway rules, standard specifications, standard details of construction and the Americans with Disabilities act standards for accessible design (ADA). Sidewalk or pedestrian walkways that cross a curb must be usable by all pedestrians, especially aging New Yorkers and persons with disabilities. Included below are terms and definitions followed by a table that explains the requirements for pedestrian ramp construction.

| Terms  | Definitions   |  |
|--|---|--|
| ADA Requirements   | ADA Title II; CFR Title 28 Part 35  |  |
| DOT Requirements   | ADA requirements are the minimum. For DOT in-house or DOT-Sponsored projects, the full intersection must be included.   |  |
| Crosswalk  | From NYC traffic rules Section 4-01(b):  (i) Marked crosswalk. That part of a roadway defined by two parallel lines or highlighted by a pa ern of lines (perpendicular, parallel or diagonal used either separately or in combina on) that is intended to guide pedestrians into proper crossing paths.  (ii) Unmarked crosswalk. That part of a roadway, other than a marked crosswalk, which is included within the extensions of the sidewalk lines between opposite sides of the roadway at an intersection, provided that (A) the roadway crosses through the intersection rather than ending at the intersection, and/or (B) all traffic on the opposing roadway is controlled by a traffic control device. |  |
| Crossing   | A crossing is a marked or unmarked crosswalk as defined above. Examples of work that would create a new crossing include when crosswalk markings are installed across the major street at a T-intersection, at a midblock location, or at a location where pedestrian crossings were previously prohibited.   |  |
| Corner   | From Mayor's Executive Order No. 22 dated April 13, 1995.<br>Corner shall mean the area created by extending the building line to the curb.   |  |
| Near midblock crosswalk                                      | The sidewalk flags that are part of or abutting a pedestrian ramp, ramp flare or ramp landing at a midblock crosswalk or, if no ramp exists, the sidewalk curb within the limits of the marked crosswalk.   |  |
| Alteration   | As defined by Accessibility Laws, can include, without limitation, any resurfacing, repaving, reconstruction or widening of streets, that affect pedestrian access to the public right-of-way.  |  |
| Roadway maintenance treatments                               | Treatments such as crack filling and sealing, surface sealing, chip seals, slurry seals, fog seals, scrub sealing, joint crack seals, joint repairs, dowel retrofits, spot high-friction treatments, diamond grinding, and spot pavement patches.   |  |
| Resurfacing  | Typical DOT resurfacing, or also microsurfacing, thin lift overlays, open graded surface courses, cape sealing, In-place asphalt recycling. Resurfacing is considered an alteration by the ADA.   |  |
| None, unless any ramps disturbed                             | Any direct interference with a ramp or blended transition, ramp flare, or ramp landing area will trigger upgrades to that specific ramp. If there is no direct interference with a ramp or blended transition, then no work is triggered.   |  |
| All ramps at disturbed corners or disturbed curb at crossing | The installation or upgrade of any required curb ramps or blended transitions located within the corner or located at a pedestrian crossing that is within the limit of work of said project or construction operation.   |  |
| Affected crosswalk (ramps on both ends)                      | The installation or upgrade of any required curb ramps or blended transitions served by a crosswalk that is within the limit of work of said project or construction operation.   |  |
| All ramps at adjoining corners or adjoining curb at crossing | The installation or upgrade of any required curb ramps or blended transitions that abut the limit of work of said project or construction operation.  |  |
| Full intersection (all corners)                              | The installation or upgrade of any required curb ramps or blended transitions that are within an intersection which is within the limit of work of said project or construction operation.  |  |

<sup>\*</sup>The term "pedestrian ramps" is used in NYC to refer to curb ramps.

Please see other side for triggers ADA triggers







## **Pedestrian Ramp Construction Triggers**

| Construction Activity   | ADA Requirements   | DOT Requirements  |
|---|--|---|
| Sidewalk  |  |   |
| Construction of new sidewalk  | All ramps at disturbed corners or disturbed curb at crossing | Full intersection (all corners)   |
| Sidewalk construction - not in corner or near midblock crosswalk                    | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Sidewalk construction - part/all of corner  | All ramps at disturbed corners or disturbed curb at crossing | Full intersection (all corners)   |
| Construction of single or double curb extension                                     | All ramps at disturbed corners or disturbed curb at crossing | Full intersection (all corners)   |
| Construction of island or median within a crosswalk                                 | Affected crosswalk (ramps on both ends)                      | Full intersection (all corners)   |
| Construction of island or median not in a crosswalk                                 | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Markings/Signals  |  |   |
| New crosswalk markings at existing crossing (see definitions)                       | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| New crosswalk markings at new or moved crossing (see definitions)                   | Affected crosswalk (ramps on both ends)                      | Affected crosswalk (ramps on both ends)   |
| Refurbishing of crosswalk markings  | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Relocation of Detectable Warning Surface  | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Installation of new signal  | None, unless any ramps disturbed                             | All ramps at disturbed corners or disturbed curb at crossing (when Turbo Crew is available) |
| Signal upgrade (e.g., installation of APS)  | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Signal maintenance or software alteration   | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Utility Work  |  |   |
| Utility trench sidewalk   | All ramps at disturbed curb at crossing                      | Full intersection (all corners)   |
| Utility trench roadway requiring curb-to-curb restoration                           | All ramps at adjoining corners or adjoining curb at crossing | Full intersection (all corners)   |
| Resurfacing   |  |   |
| Curb-to-curb resurfacing including crosswalk  | All ramps at adjoining corners or adjoining curb at crossing | Full intersection (all corners)   |
| Partial resurfacing in crosswalk  | Affected crosswalk (ramps on both ends)                      | Full intersection (all corners)   |
| Partial resurfacing outside of crosswalk  | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Roadway maintenance treatments (see definition)                                     | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Roadway Reconstruction  |  |   |
| Full width roadway reconstruction/rehabilitation including crosswalks or corner     | All ramps at adjoining corners or adjoining curb at crossing | Full intersection (all corners)   |
| Full width roadway reconstruction/rehabilitation not including crosswalks or corner | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
|   | All ramps at adjoining corners or adjoining curb at crossing | Full intersection (all corners)   |
| Transit   |  |   |
| Installation of seating at bus stop   | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Installation of bus shelter   | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Installation of bus bulb  | All ramps at disturbed corners or disturbed curb at crossing | Full intersection (all corners)   |
| Installation of bus pads  | All ramps at disturbed corners or disturbed curb at crossing | Full intersection (all corners)   |
| Construction of subway elevator and entrance  | All ramps at disturbed corners or disturbed curb at crossing |   |
| Other   |  |   |
| Installation of street furniture (other than bus shelters)                          | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Installation of wayfinding signage  | None, unless any ramps disturbed                             | None, unless any ramps disturbed  |
| Construction of public facility (e.g. park, school)                                 | All ramps at disturbed corners or disturbed curb at crossing | All ramps at disturbed corners or disturbed curb at crossing                                |
| Green infrastructure (within corner or at midblock crossings)                       | All ramps at disturbed corners or disturbed curb at crossing | All ramps at disturbed corners or disturbed curb at crossing                                |
| Rubber Island in crosswalk  | Affected crosswalk (ramps on both ends)                      | Affected crosswalk (ramps on both ends)   |